

L

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 43. NR. 29. W. . .

----- Dickinson ----- COUNTY

DESCRIPTION OF CORNER $\frac{1}{4}$ corner between sections 13 and 24 -----

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap -----

WITNESSES TO CORNER White Spruce 18" S 42 E 9 $\frac{1}{2}$ links -----
marked $\frac{1}{4}$ S NBT

Cedar 14" S 53 W 71 links -----
marked $\frac{1}{4}$ S NBT


Distances measured from center of brass cap to NBT notch.

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR
RESTORED.

Replaced corner from two probable original bearing trees. Hard Maple 28" S 64 W 35 links with overgrowth facing post. Old axe marks about 8" into tree. Original bearing tree was hard maple 12" S 64 W 35 links. Hemlock windfall, down, in place N 63 E 16 links. Remains of hemlock fit well for original which was hemlock 18 N 63 E 16 links. Found old post about 10 feet SW of corner. Corner falls on old blaze line east and west. Have good corner $\frac{1}{2}$ mile east. This half mile chained by C. Ryberg and D. Voice. Corner pointed out to me by Clarence Ryberg.

Corner placed and witnessed 15 September 1958 with C. Ryberg.

SURVEYORS SEAL


SIGNED Henry S. Peterson
REGISTERED LAND SURVEYOR

DATE 9/16/58