

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 43 N.R. 29 W


Dickinson COUNTY

DESCRIPTION OF CORNER East 1/16 corner between Sections 30 and 31

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED July 2, 1968

WITNESSES TO CORNER..... Cedar 12 S24W 128 lks. (1/16 S BT)



Cedar 10 S 6E 87 lks. (1/16 S BT)

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner was established midway on line between monuments at NE corner of Section 31 and N  $\frac{1}{4}$  corner of Section 31, as previously set from original bearing trees and now recorded in Conservation Department and Dickinson County files. Distance between Section corner and  $\frac{1}{4}$  corner found to be 39.8045 chains.

SURVEYOR'S SEAL

SIGNED Arthur O. Enger DATE 7/2/68  
REGISTERED LAND SURVEYOR