

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Dickinson COUNTY


T 43N R 28-29W

DESCRIPTION OF CORNER 1/4 corner between Section 1 and 6

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED June 19, 1969

WITNESSES TO CORNER..... Elm 8 N72°W 5 links "1/48 MBT"



Sugar Maple 6 S32 1/2°E 46 links "1/48 MBT"

Bearings are magnetic

AND _____

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument placed by proportionate measurement on line between an original 1/4 corner 80.10 chains south and an original township corner 38.80 chains north. Found no evidence of the original corner monument or its accessories or of any replacement monument or accessories.

Corner is in upland hardwoods.

SURVEYOR'S SEAL

SIGNED Arthur O. Enger DATE 2/26/70
REGISTERED LAND SURVEYOR

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68