

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Dickinson COUNTY
T 43N R 29W

DESCRIPTION OF CORNER West 1/16 corner on E & W 1/4 line, Section 36

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED August 3, 1970

WITNESSES TO CORNER..... Tamarack 6 S60°E (mag.) 7.6 ft. "1/16S, BT"



Balm-of-Gilead 5 S18 1/2° W (mag.) 18.5 ft. "1/16S, BT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner established on line between West 1/4 corner 1325.7 ft. west and Center 1/4 corner 1325.7 ft. east. No evidence that the corner had been previously established.

SURVEYOR'S SEAL

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE January 19, 1972

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68