

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Dickinson COUNTY
T 43N R 29W

DESCRIPTION OF CORNER Center of NW $\frac{1}{4}$, Section 36

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED August 5, 1970

WITNESSES TO CORNER..... Balsam 5 S45°E (mag.) 17.0 ft. "1/16S, BT"



Cedar 10 S42°W (mag.) 45.2 ft. "1/16S, BT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner established at intersection of quarter-quarter section lines.
Found no evidence of any subsequent monument, but corner falls at what appears
to have been the SW corner of an old field.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR

DATE

January 19, 1972

Arthur O. Enger

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68