

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Dickinson COUNTY
T 43N R 29W

DESCRIPTION OF CORNER 1/4 corner between Sections 25 and 36

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED July 29, 1970

WITNESSES TO CORNER..... White Birch 8 S77°E (mag.) 29.7 ft. "1/4S, NBT"



White Birch 5 N 3°E (mag.) 21.0 ft. "1/4S, NBT"

Bigtooth Aspen 10 N50°W (mag.) 17.2 ft. "1/4S, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found a 2"x2"x36" squared wood post S35°W 77 lks. for an approximate corner. Corner re-established on line between section corners 2648.7 ft. to east and to west. The found approximate corner post had been set by unknown parties near a large white pine stump with old axe marks on it, but nothing to prove it was the original BT.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE

January 19, 1972

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68