

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Dickinson COUNTY
T 43N R 29W

DESCRIPTION OF CORNER West 1/16 corner between Sections 25 and 36

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED July 29, 1970

WITNESSES TO CORNER..... W. Spruce 5 N51 $\frac{1}{2}$ ^oE (mag.) 19.6 ft. "1/16S, BT"



B. Spruce 6 N38^oW (mag.) 21.9 ft. "1/16S, BT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found a 12" aspen with blazes on 4 sides, bearing N85^oW 41 lks., for an approximate corner. Corner established on line between section corner 1324.4 ft. west and 1/4 corner 1324.4 ft. east.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE

January 19, 1972

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68