


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Dickinson COUNTY
T 43N R 29W

DESCRIPTION OF CORNER Section Corner 26, 27, 34, and 35
CORNER MONUMENT 1" I. D. x 36" iron pipe with 4" aluminum cap
DATE MONUMENT PLACED AND WITNESSED July 24, 1970
WITNESSES TO CORNER..... Cedar 10 N59°W (mag.) 23.6 ft. "S27, NBT"



Cedar 5 S69°E (mag.) 12.6 ft. "S35, NBT"
Balsam 5. S53°W (mag.) 13.7 ft. "S34, NBT"
AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found a 3"x3"x4' squared post placed between 1955 and 1960 by forestry personnel of MDNR. Corner was perpetuated as found. Also found the point of a much older post in the swamp muck, and digging still deeper, found the point of a third, very old cedar post and the well-preserved upper part of the same post lying horizontally under the moss nearby. The latter post is believed to be the original and is accepted as authentic by the undersigned. No trace of the original bearing trees. Corner position marked by several very old blazes facing the corner, on nearby trees, and was apparently protected by a pole corral which appears from remnants to have been constructed in early logging days.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR

DATE

January 20, 1972

Arthur O. Enger

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68