

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(DICKINSON COUNTY)

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 43 N. R. 29 <input checked="" type="checkbox"/> E. <input type="checkbox"/> W.	#G-10
2. PROPERTY CONTROLLING IN SECTION	27, T. 43 N. R. 29 <input checked="" type="checkbox"/> E. <input type="checkbox"/> W.	#3
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. R. _____ E. <input type="checkbox"/> W. <input type="checkbox"/>	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on December 19, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner G-10 (1/4 corner between Sections 27 & 28, T43N, R29W):
 - Spruce post (Not found. No subsequent monuments found.)
 - Y. Birch 16 S30E 12 (Not found. No subsequent accessories found.)
 - Hemlock 9 S60W 17 (Not found. No subsequent accessories found.)
 - Corner 3 (North 1/16 corner between Sections 27 & 28, T43N, R29W):
 - Not established in original survey nor subsequently, apparently.
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner G-10: Restored on line between Section Corners 40.000 ch. to N and to S. Corner falls 3.5 to 4 ch. N of swamp edge, as stated in original field notes.
 - Corner 3: Established on line between 1/4 cor. 20.000 ch. S and Sec, Cor. 20.000 ch. N. Corner is about 4.25 ch. S of a stream; the original field notes indicate the distance as being 4.50 ch. but apparently in this township the distances to streams were only recorded to the nearest half-chain.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Corner G-10: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 - Sugar Maple 6 S 2°E (mag.) 6.9 ft. "1/4S, NBT"
 - Sugar Maple 5 N77°W (mag.) 9.3 ft. "1/4S, NBT"
 - Sugar Maple 6 N62°E (mag.) 7.8 ft. "1/4S, NBT"
 - Declination 2°35' West.
 - Corner 3: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 - Sugar Maple 6 S12-1/2°W (mag.) 8.9 ft. "1/16S, BT"
 - Sugar Maple 5 N29°W (mag.) 12.8 ft. "1/16S, BT"
 - Declination 2° 15' West.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
 APPROVED AND SIGNED BY Arthur O. Enger DATE March 7, 1980
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

