

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --	(DICKINSON COUNTY) LOCATED IN --	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 43 N. R. 29 <del>X</del> W.	#H-11
2. PROPERTY CONTROLLING IN SECTION <u>27</u>	T. 43 <del>X</del> S. R. 29 <del>X</del> W.	#10
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner H-11 (1/4 corner between Sections 27 & 34, T43N, R29W):**  
 Cedar post (Not found. See B for subsequent monument.)  
 Spruce 16 S22W 16 (Not found. No subsequent accessories found.)  
 Cedar 10 S14E 15 (Not found. No subsequent accessories found.)

**Corner 10 (South 1/16 corner between Sections 27 & 28, T43N, R29W):**  
 Not established in original survey nor subsequently, apparently.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner H-11:** Restored 12-27-79 proportionately on line between Section Corners 40.787 ch. to E and to W. Found a 3" x 3" x 5' squared cedar post, 20-25 yrs. old, S5°36'E 55.9 ft., probably set by foresters for an approx. cor., as I could find no original evidence. This sec. line is some 1.17 ch. longer than the original field notes state; every feature that could be identified along it, except a swamp edge at the westerly end, seems to be roughly in proportion to this difference.

**Corner 10:** Established 12-19-79 on line between Sec. Cor. 20.000 ch. S and 1/4 cor. 20.000 ch. N.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Corner H-11:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.  
 B. Spruce 4 N66°W (mag.) 44.1 ft. "1/4S, NBT"  
 B. Ash 5 S54°W (mag.) 26.5 ft. "1/4S, NBT"  
 Cedar 10 S39°E (mag.) 81.7 ft. "1/4S, NBT"  
 Declination 2° 35' West.

**Corner 10:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.  
 W. Pine 26 N78°E (mag.) 35.0 ft. "1/16S, BT"  
 Cedar 6 N10°W (mag.) 64.0 ft. "1/16S, BT"  
 Declination 2° 30' West.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE March 7, 1980  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger  
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

