

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	(DICKINSON COUNTY) LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 43 N. R. 29 W.	#G-12
2. PROPERTY CONTROLLING IN SECTION 34	T. 43 N. R. 29 W.	#2 & 3
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner G-12 (1/4 corner between Sections 33 & 34, T43N, R29W):
 White Pine post (Not found. Found 1-1/4" I.D. iron pipe.)
 Balm-of-Gilead 5 N85W 15 (Not found. Found Cedar 7 North 67.7 ft.)
 Tamarack 9 N26E 25 (Not found. No other accessories found.)

**Corner 2 (East 1/16 corner between Sections 27 & 34, T43N, R29W) and
 Corner 3 (North 1/16 corner between Sections 33 & 34, T43N, R29W):**

Neither of these corners established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner G-12: On 12-12-79, noted this monument in place alongside an old 3" x 3-1/2" cedar post, as set and witnessed by unknown surveyor and from unknown evidence. Corner is on N side of a stream and bears N1°11.6'W 39.975 ch. from Sec. Cor. to S and S0°37.4'E 40.025 ch. from Sec. Cor. to N.

Corner 2: Established 12-27-79 on line between 1/4 cor. 20.393 ch. W and Sec. Cor. 20.393 ch. E. Found old N & S and E & W line blazes which seem to intersect about at the corner as established.

Corner 3: Established 12-18-79 on line between 1/4 cor. 20.0125 ch. S and Sec. Cor. 20.0125 ch. N.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner G-12: 1 1/4" I.D. iron pipe, projecting about 10" above ground.
 Cedar 7 North (mag.) 67.7 ft. "1/4S, NBT" Declination 2° 25' West.

Corner 2: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Cedar 6 S15°E (mag.) 15.0 ft. "1/16S, BT"
 Cedar 8 N 4°E (mag.) 12.9 ft. "1/16S, BT"
 Declination 2° 55' West. Also squared & scribed a 6" cedar N53°W 2.9 ft. (to center of tree).

Corner 3: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Cedar 10 N65°W (mag.) 21.3 ft. "1/16S, BT"
 Cedar 8 N32°E (mag.) 12.1 ft. "1/16S, BT"
 Declination 2° 00' West.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE March 7, 1980
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

