

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF -:	(DICKINSON COUNTY) LOCATED IN -:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 43 N. R. 29 <input checked="" type="checkbox"/> E. <input checked="" type="checkbox"/> W.	#G-11
2. PROPERTY CONTROLLING IN SECTION 33 _____	T. 43 N. R. 29 <input checked="" type="checkbox"/> E. <input checked="" type="checkbox"/> W.	#2
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. R. _____ E. <input type="checkbox"/> W. <input type="checkbox"/>	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on December 18, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner G-11 (Section Corner 27, 28, 33 & 34, T43N, R29W):
 Cedar post (Not found. No subsequent monuments found.)
 Sugar 12 S57E 13 (Not found. No subsequent accessories found.)
 Sugar 10 N60W 19 (Not found. No subsequent accessories found.)

Corner 2 (East 1/16 corner between Sections 28 & 33, T43N, R29W):
 Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner G-11: Restored at record distance E of Sec. Cor. 28, 29, 32 & 33 and N of Sec. Cor. 3, 4, 33 & 34. This appears to satisfy many of the calls to natural features of record, except for a swamp edge which is supposed to be 4.50 ch. E, but actually is only 3.00 ch. This location has been used for the corner for many years apparently; two large pine stumps have very old notched blazes facing the corner location, and the stump to NW has a location tag on it.
Corner 2: Established on line between 1/4 cor. 19.950 ch. W and Sec. Cor. 19.950 ch. E.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner G-11: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 White Spruce 14 S42-1/2°E (mag.) 26.6 ft. "S34, NBT"
 White Spruce 12 N27° E (mag.) 51.1 ft. "S27, NBT"
 White Pine 28 S30° W (mag.) 39.6 ft. "S33, NBT"
 Cedar 8 N36° W (mag.) 90.1 ft. "S28, NBT"
 Declination 2° 40' West.
Corner 2: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 White Pine stump 32 S59°E (mag.) 53.2 ft. "1/16S, BT"
 White Spruce 18 N83°E (mag.) 40.4 ft. "1/16S, BT"
 Declination 2° 15' West.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger CHIEF OF SURVEY PARTS DATE March 7, 1980

MICHIGAN REGISTERED LAND SURVEYOR
Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

