

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(DICKINSON COUNTY)

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____ T. <u>43</u> N. R. <u>29</u> E. W.		<u>#B-11</u>
2. PROPERTY CONTROLLING IN SECTION_____ T. _____ S. R. _____ E. W.		
3. MISCELLANEOUS PROPERTY IN SECTION_____ T. _____ S. R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on December 20, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner B-11 (1/4 corner between Sections 30 & 31, T43N, R29W):
 Cedar post (Not found. Found 1" iron pipe with 4" brass cap.)
 Cedar 16 S 7°W 30 (Not found. Found Tamarack 11 S41W 55-1/2 lks.)
 Cedar 18 N 1°W 48 (Not found. Found dead Aspen 8 S57E 9 lks.)

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

This certificate records additional witnesses, marked because the aspen NBT is dead. Present monument set by H. S. Peterson, R.L.S., on 6-5-56 from an original BT (which one is not recorded).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1" I.D. x 48" iron pipe with 4" brass cap, set by Peterson.
 Tamarack 15 S44°W (mag.) 36.4 ft. "1/4S, NBT" } Peterson's
 Aspen 12 S53°E (mag.) 6.0 ft. "1/4S, NBT" }
 Red Maple 7 N36°W (mag.) 22.8 ft. "1/4S, NBT" } Enger's
 Red Maple 3 N33°E (mag.) 7.5 ft. "1/4S, NBT" }

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE _____
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources
 SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

