

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

DICKINSON COUNTY

FOR CORNERS OF --	LOCATED IN --	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 43 N. R. 29 E. W.	E6, E8
2. PROPERTY CONTROLLING IN SECTION _____	16, T. 43 N. R. 29 E. W.	3
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on See Below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner 3: Not set on original survey nor subsequently apparently.

Corner E6: Original monument and accessories not found.

Corner E8: Found two possible B.T. stumps which match original notes for bearing and distance. Also found old choppings in muck.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner 3: Established 5-14-81 midway and on line between section corner north and $\frac{1}{4}$ corner south.

Corner E6: Restored 5-14-81 midway and on line between section corners north and south.

Corner E8: Restored 5-21-81 from two old stumps.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner 3: Set 1" I.D.x32" iron pipe with 4" alum. cap.

7" Cedar N47W 30.2 ft. $\frac{1}{16}$ S,BT

7" Ash S84W 27.2 ft. $\frac{1}{16}$ S,BT

4" Ash S08E 4.1 ft. $\frac{1}{16}$ S,BT

Corner E6: Set 1" I.D.x32" iron pipe with 4" alum. cap.

8" Spruce N63W 7.3 ft. $\frac{1}{4}$ S,NBT

3" Maple S71E 21.3 ft. $\frac{1}{4}$ S,NBT

6" Balsam S03W 29.4 ft. $\frac{1}{4}$ S,NBT

Corner E8: Set 1" I.D.x32" iron pipe with 4" alum. cap.

9" Cedar N4W 16.3 ft. $\frac{1}{4}$ S,NBT

14" Cedar N47E 37.2 ft. $\frac{1}{4}$ S,NBT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 10-22-81

CHIEF OF SURVEY PARTY
Keith L. Sackett
MICHIGAN REGISTERED LAND SURVEYOR

Keith L. Sackett
Department of Natural Resources



SURVEYOR'S MICHIGAN REGISTRATION NO. 19006