

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

DICKINSON COUNTY

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>43</u> N. <u>X</u> , R. <u>29</u> <u>X</u> W.	<u>E7, D9</u>
2. PROPERTY CONTROLLING IN SECTION	<u>16</u> , T. <u>43</u> N. <u>X</u> , R. <u>29</u> <u>X</u> W.	<u>10</u>
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. _____, R. _____ E. _____ W. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 12, 19 81, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner E7: Original monument and accessories not found.
- Corner D9: Original monument and accessories not found.
- Corner 10: Not set on original survey nor subsequently apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner E7: This corner set by proportion between $\frac{1}{4}$ corner south and section corner north.
- Corner D9: Restored midway on line between section corners east and west,
- Corner 10: Established midway and on line between $\frac{1}{4}$ corner north and section corner south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Corner E7: Set 1" I.D.x32" iron pipe with 4" alum. cap.
 - 7" Sugar N51W 8.0 ft. S17,NBT
 - 5" Sugar S85E 6.6 ft. S21,NBT
 - 7" Yellow Birch S87W 25.4 ft. S20,NBT
- Corner D9: Set 1" I.D.x32" iron pipe. Corner falls 18 ft. east of N-S county road.
 - 8" Elm N40W 59.3 ft. $\frac{1}{4}$ S,NBT
 - 12" Elm S49W 59.0 ft. $\frac{1}{4}$ S,NBT
- Corner 10: Set 1" I.D.x32" iron pipe with 4" alum. cap.
 - 5" Sugar N65E 15.3 ft. 1/16S,BT
 - 7" Sugar S28W 10.2 ft. 1/16S,BT
 - 6" Sugar N36W 19.3 ft. 1/16S,BT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 10-22-81

CHIEF OF SURVEY PART
 MICHIGAN REGISTERED LAND SURVEYOR
 Keith L. Sackett

Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

