

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	DICKINSON COUNTY LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 43 N. <del>XX</del> R. 29 <del>XX</del> W.	E4, E5
2. PROPERTY CONTROLLING IN SECTION	9 T. 43 N. <del>XX</del> R. 29 <del>XX</del> W.	3, 10
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. _____ R. _____ E. _____ S. _____ W. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 19, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner 3: Not set on original survey nor subsequently apparently.
  - Corner E4: Original monument and accessories not found.
  - Corner 10: Not set on original survey nor subsequently apparently. Found Keweenaw Land tag on 6" Elm N61W 16.8 ft.
  - Corner E5: Original monument and accessories not found. Found sq. post.
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner 3: Established midway and on line between 1/4 corner south and section corner north. Corner falls 10 ft. west of old road.
  - Corner E4: Restored midway on line between corners north and south.
  - Corner 10: Established midway and on line between section corner south and 1/4 corner north.
  - Corner E5: Restored at old post. Post fits good with other corners in area.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- |  |  |
|--|--|
| Corner 3: Set 1" I.D.x32" iron pipe with 4" alum. cap.<br>6" Balsam N82# 35.1 ft. 1/16S,BT<br>7" Balsam N18W 81.4 ft. 1/16S,BT                                 | Corner E5: Set 1" I.D.x32" iron pipe with 4" alum. cap.<br>8" Tamarack N80E 62.0 ft. S9,NBT<br>9" Tamarack N45W 16.9 ft. S8,NBT<br>7" Spruce S02W 19.5 ft. S17,NBT |
| Corner E4: Set 1" I.D.X32" iron pipe with 4" alum. cap.<br>4" Balsam N86W 22.2 ft. 1/4S,NBT<br>8" Balsam S6 1/2 E 70.8 ft. 1/4S,NBT                            |  |
| Corner 10: Set 1" I.D.x32" iron pipe with 4" alum. cap.<br>4" Balsam S35E 7.9 ft. 1/16S,BT<br>5" Balsam N5E 13.0 ft. 1/16S,BT<br>6" Elm N61W 16.8 ft. 1/16S,BT |  |

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Keith L. Sackett DATE 10-22-81

CHIEF OF SURVEY PARTY  
 MICHIGAN REGISTERED LAND SURVEYOR  
 Keith L. Sackett  
 Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

