

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Bickinson

(County)

Located in:

Corner Code ##

1. Public Land Survey	T	<u>43N</u>	R	<u>29W</u>	<u>00</u>	
	T	<u>43N</u>	R	<u>29W</u>	<u>10</u>	
	T	_____	R	_____	_____	
	T	_____	R	_____	_____	
2. Property Controlling in Section	S	<u>15</u>	T	<u>43N</u>	R	<u>29W</u>
	S	_____	T	_____	R	_____
3. Miscellaneous Property in Sec.	S	_____	T	_____	R	_____
	S	_____	T	_____	R	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

7 April 27, 1994

10 April 27, 1994

I, Stephan J. Szyszkoski, in a field survey on 68 April 25, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	6	5	4	3	2	1						
5													
6	10	9	8	7	6	5	4	3	2	1			
7													
8	13	12	11	10	9	8	7	6	5	4	3	2	1
9													
10	16	15	14	13	12	11	10	9	8	7	6	5	4
11													
12	19	18	17	16	15	14	13	12	11	10	9	8	7
13													

A. Description of original monument and accessories and/or subsequent restoration:

(00) Quarter corner common to Sections 15-16. Original corner established in 1848 by Harvey Mellon as follows: Set cedar post. White Pine 20 N24E 24, White Pine 18 S27W 4. Original line notes show: 1) South 5.95 ch. Stream & C. east, 2) North 3.74 ch. Cedar 10, 3) North 7.00 Enter alder swamp C. NE. Found no subsequent record.
 (10) Quarter corner common to Sections 14-15. Original corner established in 1848 by Harvey Mellon as follows: Set cedar post. Hemlock 12 S30W 20, Sugar 12 N54E 10. Found no subsequent record.
 (7-Sec. 15) North 1/10 corner between Sections 14-15. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(00) Re-monumented the corner at record bearing and distance from the remains of the original bearing trees: White pine stumps of proper size in advanced stages of decay N24E 24 links, and S27W 4 links. No markings visible. The stumps showed evidence of heavy burning. Stream crossing to south and Enter Swamp to north check as recorded above. Found no trace of the Cedar line tree. At the position for the corner, I placed a 1" I.D. x 32" iron pipe capped with a 4" dia. cast aluminum MDMR tablet, appropriately stamped.
 (10) Original post and accessories not recovered. Found no monumentation at the corner position. Found no acceptable evidence on the ground of the position of the original corner. Reestablished the corner midway and on a straight line between monumented section corners 2050.05' north and south. At the position for the corner, I placed a 1" I.D. x 32" iron pipe capped with a 4" dia. cast aluminum MDMR tablet, appropriately stamped.
 (7-Sec. 15) Found no evidence of prior monumentation at the corner position. Established the corner on a straight line between Section corner 1325.33' North and Quarter corner 1325.33' South. At the position for the corner, I placed a 1" I.D. x 32" iron pipe capped with a 4" dia. cast aluminum MDMR tablet, appropriately stamped.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(00) Set 1" pipe with 4" MDMR cap. Blazed and scribed the following new bearing trees: 4" Spruce S80W 5.0' *1/4S NBT* 12" Spruce N20W 10.7' *1/4S NBT* 20" Spruce N56E 13.5' *1/4S NBT* 0" Spruce S00E 22.6' *1/4S NBT* Set a 3" squared cedar post adjacent. Bearings are magnetic.	(10) Set 1" pipe with 4" MDMR cap. Blazed and scribed the following new bearing trees: 4" W. Birch N10W 21.1' *1/4S NBT* 5" Sugar N07E 26.7' *1/4S NBT* 7" Sugar S35E 45.3' *1/4S NBT* 4" W. Birch S13W 31.2' *1/4S NBT* Squared a 12" Aspen N43W 3.5'. Bearings are magnetic.	(7) Set 1" pipe with 4" MDMR cap. Blazed and scribed the following bearing trees: 7" Spruce S80W 27.0' *1/10S BT* 2" Spruce N55W 26.5' *1/10S BT* 7" R. Pine N24E 42.9' *1/10S BT* 5" W. Pine N01E 54.3' *1/10S BT* Squared a 10" Aspen, South 2.0' Distances are horizontal, bearings are magnetic.
---	--	---

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

