

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Dickinson

(County)

Located In:

Corner Code \neq

1. Public Land Survey	T	_____	R	_____	_____		
	T	_____	R	_____	_____		
	T	_____	R	_____	_____		
	T	_____	R	_____	_____		
2. Property Controlling in Section	S	<u>15</u>	T	<u>43N</u>	R	<u>29W</u>	<u>5</u>
	S	_____	T	_____	R	_____	_____
3. Miscellaneous Property in Sec.	S	_____	T	_____	R	_____	_____
	S	_____	T	_____	R	_____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		6		5		4		3		2		1
5													
6	8		7		6		5		4		3		2
7													
8	9		8		7		6		5		4		3
9													
10	10		9		8		7		6		5		4
11													
12	11		10		9		8		7		6		5
13													

I, Stephan J. Szyszkoski, in a field survey on June 02, 1994, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(5-Sec.15) North 1/16 corner, Section 15. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(5-Sec. 15) Found no evidence of prior monumentation at the corner position. Established the corner on a straight line between Center of Section 1322.40' South and Quarter corner 1322.40' North. At the position for the corner, I placed a 1" I.D. x 32" iron pipe capped with a 4" dia. cast aluminum MBR tablat, appropriately stamped. I found a 2" iron pipe, projecting about 3', bearing N73W, 60.55' from the corner monumented. Do not know who placed that pipe or why.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(5) Set 1" pipe with 6" MDRR cap.
 Blazed and scribed the following bearing trees:
 6" Spruce S39E 46.3' 1/16S BT"
 4" Spruce S53W 20.8' 1/16S BT"
 4" Spruce N60W 26.2' 1/16S BT"
 7" R. Pine N95E 81.3' 1/16S BT"
 Placed a location poster on a 6" Aspen
 N84E 8.4'. Bearings are magnetic.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 7-14-1994