

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Dickinson
County

Located In:

Corner Code #

- 1. Public Land Survey T _____ R _____
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S 36 T 43N R 29W 3
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	1	2	3	4	5	6	7	8	9	10	11	12	13
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	19	20	21	22	23	24				
7													
8	16	20	21	22	23	24							
9													
10	30	28	29	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on August 01, 1994, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(3-Sec. 36) North 1/16 corner between Sections 35-36. Corner established in 1972 by Arthur D. Enger ALS as follows: Placed 1" I.D.x36" iron pipe with 3" aluminum cap on line between section corner 1310.5' north and 1/4 corner 1310.5' south. Corner is on south edge of Co. Rd. Balsam 8 S10E 49.5', Red Maple 6 S50W 31.1'. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(3-Sec. 36) Found the 1972 monument in poor condition, the top 18" being bent over. Placed a new monument, a 1" I.D.x32" iron pipe capped with a 4" cast aluminum MNRR tablet, appropriately stamped, in the original hole and at record bearing and distance from the Red Maple 8T, found in good condition. Marked three new witnesses as described below. The centerline of an E-W county road is north 13' from the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(3) Set 1" pipe with 4" MNRR cap. Blazed and scribed the following bearing trees:
5" Sugar S94W 46.6' "1/16S NBT"
7" Sugar S87E 44.5' "1/16S NBT"
Above distances are to measuring nails found the the side of the NBTs as placed by unknown surveyor.
12" Spruce N26E 53.0' "1/16S NBT"
distance to notch. Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 9-21-94
Surveyor's Michigan License No. 33986