

MAY 07 1997

COMMISSION

RECORDED

1996 SEP 11 PM 2:30

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Form with fields for 'For corners in Dickinson (County)', 'Located In:', 'Corner Code #', and numbered sections 1-5 for survey details.

REGISTER OF DEEDS
DICKINSON COUNTY
REMONUMENTATION 49801

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 1-13, used for recording corner locations.

I, James H. Moore, in a field survey on May 30, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- D-1 North 1/4 Section 5 Cedar Post by John Burt 1846 Original Bearing Trees Cedar 14" N64E 32 LKS Cedar 10" N57W 33 LKS
C-1 North West Corner Section 5 Spruce Post by John Burt 1846 Original Bearing Trees Spruce 3" N38E 44 LKS Tamar 5" N75 1/2 W 146 LKS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- D-1 No evidence of Original Corner or Accessories Remain Found 1 1/2" O.D. Pipe projecting about 8"
C-1 No evidence of Original Corner or Accessories Remain Found 1 3/8" O.D. Pipe projecting about 6" Corner previously recorded by Thomas O'Brien, P.S. 21274, March 4, 1977

ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 9-9-96 RFP COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- D-1 Accepted above described Corner Replaced 1 1/2" O.D. Pipe with 2 1/2" stamped D.C. Remon. Corner New Witnesses Carsonite Stake South 3.0' Balsam 6" N38W 24.03' Balsam 5" N47E 18.15' Cedar 6" S70E 21.37' Cedar 4" S54W 8.63'
C-1 Accepted above described Corner Replaced 1 3/8" O.D. Pipe with 2 1/2" stamped D.C. Remon. Corner New Witnesses Carsonite Stake South 2.0' Tamarack 3" N37W 77.87' Tamarack 3" N8W 50.47' Tamarack 4" S62W 55.10' Tamarack 3" S68E 19.15'

Signed by James H. Moore, Surveyor's Michigan License No. 28423

Date July 2, 1996