

SURVEY & REMONUMENTATION

APR 27 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Dickinson
(County)

Located In:

Corner Code //

1. Public Land Survey T 43N R 30W G-4 & G-5
 T ___ R ___
 T ___ R ___
 T ___ R ___
2. Property Controlling S ___ T ___ R ___
 In Section S ___ T ___ R ___
3. Miscellaneous S ___ T ___ R ___
 Property in Sec. S ___ T ___ R ___
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

REGISTER OF DEEDS
 REGISTERED COUNTY
 REGISTERED COUNTY

1994 SEP -8 AM 8:52

RECORDED

Register of Deeds Stamp & File Number

I, Edward Kazianka, in a field survey on September 2, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-4 Wood Post Hemlock 14 S42E 22 lks. Y. Birch 16 N37W 20 lks.

G-5 Wood Post Spruce 8 S67E 43 lks. Cedar 10 N62W 33 lks.

ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON

9-7-94
R.C.F.

COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-4 No evidence of original corner or accessories found. Set Quarter Corner by proportionate measurement at the mid-point and on line between the section corners 1/2 mile to the north and south.

G-5 No evidence of the original corner or accessories found. Thus, set the corner by proportionate measurement. For north-south position: Section corners 1 mile north and south are in with a distance of 10,619.56 feet between them. Proportionately then the corner should be set 5309.78 feet south of the corner common to Sections 3, 4, 9 and 10. For east-west position: Section corners 1 mile east and west are in with a distance of 10,583.01 feet between them. Proportionately then the corner should be set 5305.41 feet east of the corner common to Sections 8, 9, 16 and 17. Thus, set the section corner at the above noted position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-4 Set a 7/8 inch by 18 inch iron pin near the centerline of the black-top county road. Maple Clump N08W 49.65 feet. Aspen 6 N29E 32.36 feet. Maple 6 S24E 39.90 feet. Maple 5 S15W 36.52 feet. A Dickinson County Survey cap stamped "W.C. 1/4 9 | 10 33' SOUTH". North 33.00 feet.

G-5 2 1/2 inch Dickinson County Survey cap on a three foot Aluminum rod. Cedar 6 S60W 52.78 feet. Cedar 6 S44W 57.37 feet. Cedar 3 S73E 74.70 feet. Tamarack 7 N66W 54.83 feet

Signed by Edward Kazianka

Date September 6, 1994

Surveyor's Michigan License No. 14765

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 23, 1971
 14765
 REVISED JAN. 1988



Liber 2 Page 103