

12

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 43 NR 30 W

Dickinson

COUNTY

DESCRIPTION OF CORNER Section corner common to sections 15,16,21 and 22

DESCRIPTION OF CORNER MONUMENT 3/4" iron rod

WITNESSES TO CORNER 16" Cedar N 75 E 39 links marked S 15 NBT

No other witness trees available

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Re-witnessed section corner as set by unknown surveyor

Found 3/4" iron rod in place. White pine stump bears S 28 E at 16 links as per Government notes for original witness tree., which was a 36" white pine. Evidence of overgrowth and scar tissue on stump. No scribe marks present. Old fence line north from corner and survey line to south. County road built to west along section line.

Corner witnessed 15 April 1958 with Clarence Ryberg.

SURVEYORS SEAL

Henry S. Peterson

SIGNED Henry S. Peterson
REGISTERED LAND SURVEYOR

DATE 4/18/58