

7

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Dickinson

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>43N</u> R <u>30W</u>	A1
	T <u>43N</u> R <u>30W</u>	A3
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Stephan J. Szyszkoski, in a field survey on May 10, 1994, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE:** Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	B	C	D	E	F	G	H	I	J	K	L	M
2	1	2	3	4	5	6	7	8	9	10	11	12
4	7	8	9	10	11	12	13	14	15	16	17	18
6	13	14	15	16	17	18	19	20	21	22	23	24
8	19	20	21	22	23	24	25	26	27	28	29	30
10	25	26	27	28	29	30	31	32	33	34	35	36
12	31	32	33	34	35	36						
13												

**A. Description of original monument and accessories and/or subsequent restoration:**

(A1) Corner common to Townships 43-44N, Ranges 30-31W. Corner previously recorded by Neal Sperrhake in 1963 as restored by proportionate measurement. Corner was monumented by a 1" I.D. x 30" iron pipe with aluminum Kimberly-Clark cap and the following NBTs: Balsam 5 S50W 82 links, W. Birch 5 S30E 84 links, Black Ash 12 N78E 175 links, Black Ash 4 N40W 87 links. Corner also recorded in 1977 by Thomas P. O'Brien who found Sperrhake's monument. Also recorded in 1988 by Xiath Sechett who found the Sperrhake monument.  
(A3) Section corner common to Sections 1-12, T43N-R31W and Sections 6-7 T43N-R30W. Corner previously recorded by Neal Sperrhake in 1962 L.2(vol.8)-P.247 as monumented by a 1"x30" iron pipe with aluminum Kimberly-Clark cap and the following NBTs: B. Ash 11 N33W 37 links, Spruce 7 S51W 32 links. Corner subsequently recorded by Thomas P. O'Brien in 1977 as: Found pipe with Kimberly-Clark cap, 12" Twin Spruce S47W 20.8', 12" Maple N34W 24.0'.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(A1) Found the 1963 monument slightly disturbed by road construction, leaning southeasterly. Forced monument into upright position so that it was in accord with the two remaining 1963 NBTs: Balsam 5 S50W 82 links, now a 9" standing snag, and Black Ash 4 N40W 87 links, now 6" in good condition. The other two 1963 NBTs are gone - the birch dead and down, the ash destroyed by road construction. Also checked the 1968 NBTs as shown below.  
(A3) Found and accepted a 1" pipe with K-C cap as described above, in good condition. Remeasured to the 1962 NBTs (The spruce now a 14" stump with measuring notch visible) and marked 3 new NBTs as described below. Did not identify the Maple NBT by O'Brien.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(A1) Found 1" pipe with aluminum Kimberly-Clark cap. Remeasured to the previously established 1968 NBTs:  
7" balsam N61W 26.1'  
12" Maple S03W 40.8'  
4" Ash S78E 25.5'

(A3) Found 1" iron pipe with aluminum Kimberly Clark cap.  
12" B. Ash N31W 23.7' scribing visible  
14" Spruce stump S52W 20.8'  
Blazed and scribed the following new bearing trees:  
10" Spruce N20E 29.8' \*86 NBT\*  
5" Spruce S47E 26.4' \*87 NBT\*  
12" Balsam S60W 45.8' \*812 NBT\*  
A 6" black ash with champion poster bears N80W 8.9'



Signed by Stephan J. Szyszkoski Date 6-16-94  
Surveyor's Michigan License No. 33986