

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 44 & 45 N.R. 27 W


Dickinson & Marquette COUNTY

DESCRIPTION OF CORNER 1/4 Corner for Sections 31 T 45 N R 27 W
6 T 44 N R 27 W

CORNER MONUMENT One 1/2" x 12" Reinforcing rod buried 1 ft. below ground level and
one, same size, at ground level, in south wheel track of woods road.

DATE MONUMENT PLACED AND WITNESSED 10-30-63

WITNESSES TO CORNER..... 9" Elm (1/4S)(NBT) N 10° E 15 1/2 links



12" Elm (1/4S)(NBT) N 79° E 41 1/2 links

12" Basswood (1/4S)(NBT) S 21° W 32 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was placed on line and the single proportioned measurement between Section Corners.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE April 13, 1964
REGISTERED LAND SURVEYOR
Billy D. Buckler