

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44N</u> N. S., R. <u>27W</u> E. W.	A-8, A-7.
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 17, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

A-8. West 1/4 corner of Section 19. Cedar post. Y. Birch 14 - S69W, 28 Lks.
 Fir 9 - N20E, 4 Lks.
 A-7. NW sec. cor. of Section 19. Cedar post. Spruce 10 - S30°W, 41 Lks.
 Do 10 - N58°E, 19 Lks.
 Cedar 12 - S45°E, 40 Lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

A-8. Set M.P.O.L. between the NW and SW sec cors. of Section 19.

A-7. Set by single prop. measurement to the G.L.O. record using the positively identified "east corner" of "a granite rock boulder 20 ft. long and 15 ft. wide and 7 ft. high".
 Recorded as being 9.75 chains north of this sec. cor. and the SW sec. cor. of Section 19.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-8. 1" pipe, 4" alum. cap.	A-7. DNR Monument
10" balsam fir S27°W 35.35'	20" W. Pine - N1°W, 63.8'
2" sugar maple N40°W 10.65'	6" Maple - N51°W, 47.9'
10" sugar maple N54°E 14.25'	7" Aspen - S84°W, 39.7'
3" sugar maple S32°W 21.70'	S. Westerly point on what appears to be about a 1/2 cu. yd. boulder mostly buried beside a 1" Bl. Cherry. } S32°E, 17.5'

SIGNED BY

David B. Babbitt

DATE

1-16-85

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY

DATE