

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>44N</u> N. S., R. <u>27W</u> E. W.	C-7, B-7.
2. PROPERTY CONTROLLING IN SECTION	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 17, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
 C-7. NE sec. cor. of Section 19. Cedar post. Cedar 18, S59°E, 35 Lks.
 Do 10, N49°W, 26 Lks.

B-7. North 1/4 cor. of Section 19. Cedar post. Cedar 10, S45°W, 17 Lks.
 Do 10, N52°E, 8 Lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
 C-7. Set by double proportion using sec. cors. 1 mile west, 1 mile north and 1 mile south and the 1/4 cor. 1/2 mile east.

B-7. Set by single proportion between the NW and NE sec. cors. of Section 19.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 C-7. 1" pipe 4" alum. cap. B-7. 1" pipe, 4" alum. cap.
 10" spruce N34°E, 4.45' 4" balsam fir, N79°E, 18.5'
 14" spruce N40°E, 20.05' 5" black spruce, S22°E, 38.0'
 8" spruce N63°E, 48.00' 5" black spruce, N84°W, 35.9'
 7" spruce S56°E, 39.60' 4" balsam fir, S88°E, 63.3'

SIGNED BY David B. Babbitt DATE 1-10-85

SURVEYOR'S MICHIGAN REGISTRATION NO. RLS 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____