

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>44N</u> N. S., R. <u>27W</u> E. W.	C-6, C-5.
2. PROPERTY CONTROLLING IN SECTION	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 17, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

C-6. East 1/4 corner of Section 18. Ironwood post. Sugar 14, N53°E, 24 Lks.
Do 16, S69°W, 23 Lks.

C-5. Northeast sec. cor. of Section 18. Wood post. Cedar 16, S66°W, 17 Lks.
Do 7, N21°E, 17 Lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

C-6. Set M.P.O.L. between the NE and SE sec. cors. of Section 18.

C-5. Being unable to find any established corner positions and no evidence of the original government survey for more than a mile in any direction, I have re-established this sec. cor. at record dist. south (3.50 chs.) from a very definite swamp edge, record dist. west (1.60 chs.) from a foot of hill, record dist. east (3.00 chs.) from the top of a narrow N-S ridge and record dist. north (1.00 chs.) from a top of ridge. Other feature calls in all directions fit well and mea. to known corners in the area are reasonable.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-6. 1" pipe, 4" alum. cap.	C-5. 1" pipe and 4" alum. cap.
10" sugar maple N81°W, 42.7'	4" balsam fir S58°W, 21.2'
11" sugar maple N61°E, 27.4'	4" aspen N38°W, 6.7'
9" balsam fir S25°E, 23.35'	8" balsam fir N59°E, 20.1'
14" sugar maple S36°W 16.1'	12" balsam fir S24°E, 6.7'

SIGNED BY

David B. Babbitt

DATE

1-16-85

SURVEYOR'S MICHIGAN REGISTRATION NO.

RLS 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY

DATE