

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. _____ N. _____ S., R. _____ E. _____ W. _____		
2. PROPERTY CONTROLLING IN SECTION _____ , T. <u>44N</u> N. <u>27W</u> E. _____ S., R. _____ W. _____		<u>1, 8, 4.</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____ , T. _____ N. _____ S., R. _____ E. _____ W. _____		
4. LOT NO. _____ , RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 17, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 1) West 1/16 cor. on north section line of Section 19. Not previously est.
- 8) West 1/16 cor. of Section 19. Not previously est.
- 4) Northwest 1/16 cor. of Section 19. Not previously est.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 1) Set by single proportion betw. the NE 1/4 cor. and the NW sec. cor. of Section 19.
- 8) Set by single prop. between the W1/4 cor. and the center of Section 19.
- 4) Set at the computed center of the NW 1/4 of Section 19.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | |
|----------------------------|---------------------------|---------------------------|
| 1) 1" pipe, 4" alum. cap. | 8) 1" pipe, 4" alum. cap. | 4) 1" pipe, 4" alum. cap. |
| 10" s.maple S70°E, 17.65' | 3" bl.cherry N46°W, 11.0' | 4" b.spruce, S61°E, 2.4' |
| 22" s.maple S35°W, 35.4' | 4" aspen N25°E, 13.8' | 4" b.spruce, S32°W, 5.9' |
| 6" balsam fir N86°W, 24.4' | 4" aspen S27°E, 13.7' | 4" b.spruce, N28°E, 2.9' |
| 4" bl.cherry N4°E, 22.4' | 6" aspen S25°W, 8.0' | 4" b.spruce, N38°W, 2.0' |
- Monument 2' east of East Wheel Track.

SIGNED BY

David B. Babbitt

DATE

1-16-85

SURVEYOR'S MICHIGAN REGISTRATION NO. RLS 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY

DATE