

of B. B. 12

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Dickinson</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>6</u> T <u>44N</u> R <u>27W</u>	<u>10, 3.</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, David Babbitt in a field survey on 8/4/87, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:  
10. South 1/16 corner on the west section line of Section 6.  
3. North 1/16 corner on the west section line of Section 6.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
10. Set MPOL between the west 1/4 corner and the SW section corner of Section 6.  
3. Set by single proportion to the GLO record between the west 1/4 corner and the NW section corner of Section 6.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
10. DNR Monument.  
14" oak, N45W, 31.7'  
6" sugar maple, S60E, 11.35'  
5" sugar maple, S13E, 29.6'  
8" sugar maple, S83W, 41.15'  
3. DNR Monument  
15" cedar, S75W, 27.9'  
12" cedar, N34W, 43.5'  
14" maple, N37E, 15.1'  
13" spruce, S37E, 44.8'

Signed by David B. Babbitt Date 12-3-87  
Surveyor's Michigan License No. 21558