

OK  
B. Babbitt

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Dickinson  
(County)

Located In:

Corner Code  $\neq$

1. Public Land Survey

T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling  
in Section

S 18 T 44N R 27W  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

1, 2, 10, 3.

3. Miscellaneous  
Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, David Babbitt, in a field survey on 8/18/87, 19 \_\_\_\_\_

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1. West 1/16 on north section line of Section 18. No previous record.
2. East 1/16 on north section line of Section 18. No previous record.
10. South 1/16 on the west section line of Section 18. No previous record.
3. North 1/16 on west section line of Section 18. No previous record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1. Set by single proportion to the GLO record between the NW section corner and the N $\frac{1}{2}$  corner of Section 18.
2. Set MPOL between the NE section corner and the N $\frac{1}{2}$  corner of Section 18.
10. Set MPOL between the west 1/4 corner and the SW section corner of Section 18.
3. Set MPOL between the west 1/4 corner and the NW section corner of Section 18.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |                        |                        |                           |
|------------------------|------------------------|---------------------------|
| 1. DNR Monument        | 2. DNR Monument        | 10. DNR Monument          |
| 10" w.pine S23W, 16.5' | 8" spruce N18W, 11.2'  | 8" h.maple, N15E, 12.5'   |
| 9" w.pine N21W, 13.5'  | 10" balsam S86E, 15.7' | 10" h.maple, S74E, 38.95' |
| 12" w.pine S80E, 20.0' | 3" aspen, S23W, 4.6'   | 14" h.maple, S69W, 10.9'  |
| 11" w.pine S75W, 8.7'  | 8" spruce, N70W, 48.4' | 8" h.maple, N76W, 45.4'   |

3. DNR Monument
- 9" spruce, S35W, 1.35'
- 4" w.pine, N68W, 14.8'
- 10" w.pine, N1W, 4.5'
- 5" sugar maple, S77E, 17.3'

Signed by David B. Babbitt

Date 12-3-87

Surveyor's Michigan License No. 21558