

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Dickinson
 (County)

Located In: Corner Code #

1. Public Land Survey	T <u>44N</u> R <u>27W</u>	<u>K5</u>
	T <u>44N</u> R <u>27W</u>	<u>MC HI-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Jul 09 2001

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5			4		3		2		1	
3													
4		7	8			9		10		11		12	
5													
6		18	17			16		15		14		13	
7													
8		19	20			21		22		23		24	
9													
10		30	29			28		27		26		25	
11													
12		31	32			33		34		35		36	
13													


A. Description of original monument and accessories and/or subsequent restoration:
 (K5) Corner common to Sections 11-12-13-14. Perpetuated in 1959 and recorded in 1960 by Billy D. Buckler RLS: "This corner was replaced from one W.Pine 8.T. (down) and badly rotted. Bearing N37E 47 links. Found several scribe marks and overgrowth. 1" pipe with 4" brass cap. 14" W.Pine S56W 21 links."
 (MC HI-11) Meander corner on Township line on west side of Kates Lake. Remonumented in the original position from original W.Pine 8T and recorded in 1957 by Billy D. Buckler, RLS. 1" pipe with 4" brass cap. 16" Soft Maple S13E 62 links, 13" Tamarack N66W 78 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K5) Recovered the 1959 monument as described, in good condition, projecting about 3' a.g., and at record bearing and distance from a large dead W.Pine with large scar or blaze but no scribing visible. Distance East to monumented section corner fits well with the original record. Accepted the monument as a careful and faithful perpetuation of the position of the original corner. This corner falls in the ground path of a June, 2000 tornado. Nearly all trees in this area have been windthrown.
 (MC HI-11) Recovered the 1957 monument as described, in good condition, projecting about 2' a.g., and at record bearing and distance from the remains of the original W.Pine 8T, found N44W 27.9", being a stump with "8T" and notch plain, and from the 1957 witnesses: the maple a dead stub and the tamarack in good condition with overgrown blaze. Left the monument in place and made new witnesses as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K5) Found 1" ID iron pipe with 4" brass MDOC cap. Blazed and scribed:	(MC HI-11) Found 1" ID iron pipe with 4" brass MDOC cap. Blazed and scribed:
9" J. Pine N43E 69.4' "S12 NBT"	7" Balsam N33E 2.8' "MC NBT"
5" W.Spruce N77E 58.1' do	7" Balsam S19E 32.3' do
13" W.Spruce N74W 95.9' "S11 NBT"	8" B.Spruce N16W 40.9' do
22" W.Pine N31W 123.7' do	16" Tam. N56W 50.8' (the 1957 NBT)
Sq'd cedar post adjacent. Bearings are magnetic. Distances to notch in lower blaze.	Sq'd cedar post adjacent. Bearings are magnetic. Distances to notch in lower blaze.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 8/8/01

For the Michigan Department of Natural Resources - Forest Management Division