

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Dickinson

(County)

Located In:

Corner Code #

**1. Public Land Survey**

T	44N	R	27W	13
T	44N	R	27W	12
T		R		
T		R		

**2. Property Controlling in Section**

S		T	R	
S		T	R	
S		T	R	
S		T	R	

**3. Miscellaneous Property in Sec.**

**4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_**  
**5. Private Claims \_\_\_\_\_**

12 Oct 16 2001  
 13 Oct 25 2001

I, Paul R. Bressette, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**Register of Deeds Stamp & File Number**

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3	●	2		1	
3								●				
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

**A. Description of original monument and accessories and/or subsequent restoration:**

(13) Section corner common to Sections 2, 3, 10 and 11. 1850: John Burt, DS. Set wood post witnessed by: S.Pine 9 N46E 14 lks.; S.Pine 10 S49W 26 lks. 1952: Dean Delamater, RLS. Set 1" iron pipe with 4" brass cap from 2 original bearing trees witnessed by: 10" W.Pine S12E 35 lks.; 24" W.Pine N29E 80 lks.

(12) Quarter corner common to Sections 2 and 3. 1850: John Burt, DS. Set wood post witnessed by: S.Pine 10 S41W 30 lks.; S.Pine 10 N79E 26 lks.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(13) Found monument and witnesses as described. Southeast NBT is live and standing with both faces closed, northeast NBT is down. Both original bearings still evident, northeast OBT is a 3 foot high stump (N52E 8.3'), southwest OBT is a dead stub about 30 feet high (S50W 16.9'). Monument was rewitnessed as found, and is accepted as a careful and faithful PERPETUATION of the position of the original corner.

(12) No evidence of original survey or subsequent restoration found. Corner position reestablished by single proportion between the Southwest corner of Section 2 and the Meander corner on the line between Sections 2 and 3, and is accepted as a careful and faithful REESTABLISHMENT of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(13) 1" Iron pipe w/ 4" brass cap	(12) DNR monument
22" W.Pine N27E 13.9' (S2,NBT)	06" B.Spruce N13E 22.0' (1/4S,NBT)
23" W.Pine S78E 47.15' (S11,NBT)	07" B.Spruce N70E 11.75' (1/4S,NBT)
22" W.Pine S06E 23.9' (EX. NBT)	11" Tamarack S08W 6.9' (1/4S,NBT)
18" R.Pine N68W 20.1' (S3,NBT)	05" B.Spruce N69W 13.15' (1/4S,NBT)
All trees are blazed, scribed and painted. Measurements are to nail in side of tree, bearings are magnetic.	All trees are blazed, scribed and painted. Measurements are to nail in side of tree, bearings are magnetic.



Signed by Paul R. Bressette  
 Surveyor's Michigan License No. 37270

Date \_\_\_\_\_

For the Michigan Department of Natural Resources - Forest Management Division