

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Dickinson

(County)

Located In:

Corner Code #

1. Public Land Survey

T 44N R 27W

J3

T R

T R

T R

2. Property Controlling  
in Section

S T R

S T R

3. Miscellaneous  
Property in Sec.

S T R

S T R

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Oct 10 2001

I, Paul R. Bressette, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

|    |    |   |    |   |    |   |    |   |    |   |    |   |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| A  | B  | C | D  | E | F  | G | H  | I | J  | K | L  | M |
| 1  |    |   |    |   |    |   |    |   |    |   |    |   |
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |
| 3  |    |   |    |   |    |   |    |   | ●  |   |    |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |

A. Description of original monument and accessories and/or subsequent restoration:

(J3) Quarter corner common to Sections 2 and 11. 1850: John Burt, DS. Set wood post witnessed by: Tamarack 5 S43E 16 lks.; Tamarack 4 N51W 14 lks. Found old wood post.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J3) No evidence of original survey found. Found old squared wood post, down in poor condition. Measured east to a definite edge of swamp, call fits fairly well (GLO 2.02 ch.-133', measured 147'). The terrain calls in this township were taken on the random lines, so a true distance from corner to call is not known. The distance west to corner set from original bearing trees measures 2644.72 feet--40.07 chs.; GLO 40.48 chs.--2671.7'. Distance east to a found iron pipe measures 2775.80'--42.06 chs.; GLO 40.48 chs.--2671.7'. This places the possibility of a 2 chain error in the east half mile. Single proportion would place the corner 81 feet west of the swamp edge, a difference of 52 feet from the record. This position was rejected. Based on the evidence found, the wood post was replaced with a DNR monument, witnessed, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J3) DNR monument  
 5" B.Spruce N83E 10.15' (1/4S,NBT)  
 7" B.Spruce S64E 14.3' (1/4S,NBT)  
 7" B.Spruce S02W 16.5' (1/4S,NBT)  
 5" B.Spruce N24W 5.7' (1/4S,NBT)

All trees are blazed, scribed and painted. Measurements are to nail in side of tree, bearings are magnetic.



Signed by Paul R. Bressette  
 Surveyor's Michigan License No. 37270

Date \_\_\_\_\_

For the Michigan Department of Natural Resources - Forest Management Division