

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Dickinson

(County)

Located In:

Corner Code #

1. Public Land Survey

T 44N R 27W K3

T R _____

T R _____

T R _____

2. Property Controlling in Section

S T R _____

S T R _____

3. Miscellaneous Property in Sec.

S T R _____

S T R _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Oct 10 2001

I, Paul R. Bressette, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3										●		
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

(K3) Section corner common to Sections 1,2,11 and 12. 1850: John Burt, DS. Set wood post witnessed by: Tamarack 9 N35E 22 lks.; Tamarack 7 S76W 42 lks. Found 1 3/4" iron pipe, not of record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K3) No positive evidence of original survey found. Found 1 3/4" iron pipe. Found tamarack roots in approximate position of SW'ly original bearing tree. Distance east to stream crossing checks fairly well (GLO 18.70 ch.-1234', measured 1255'). Terrain calls in this township were taken on the random lines, so true distance from corner to call is not known. Restoration of quarter corners north and east fit calls fairly well using the pipe. To the north the quarter corner falls 92' north of the stream in line with a bend. To the east the quarter corner falls in a tamarack swale. Double proportion places the corner southwest of the pipe. This places the quarter corner north in a position that would not hit the stream and the quarter corner east on a pine ridge. Distance west to an original corner measures long (GLO 5343.4', measured 5420.50'). A found wood post for the quarter corner west places a possible 2 chain error in the east half of the line (2644.72'-40.07 ch. west half, 2775.80'-42.06 ch. east half). Distance south to an original corner also measures long (GLO 5280', measured 5306.36'). Based on the evidence found and the measurements, the 1 3/4" pipe was replaced with a DNR monument, witnessed, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- (K3) DNR monument
- 6" Balsam N68E 8.4' (S1,NBT)
- 6" W.Birch S64E 31.4' (S12,NBT)
- 5" Balsam S36W 7.9' (S11,NBT)
- 6" B.Spruce N22W 11.05' (S2,NBT)

All trees are blazed, scribed and painted. Measurements are to nail in side of tree, bearings are magnetic.



Signed by Paul R. Bressette
 Surveyor's Michigan License No. 37270

Date _____

For the Michigan Department of Natural Resources - Forest Management Division