

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Dickinson
 (County)

Located In:

Corner Code #

1. Public Land Survey

T 44N R 27W	K2
T 44N R 27W	L3
T R	
T R	

2. Property Controlling in Section

S T R	
S T R	

3. Miscellaneous Property in Sec.

S T R	
S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Oct 15 2001

I, Paul R. Bressette, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- (K2) Quarter corner common to Sections 1 and 2. 1850: John Burt, DS. Set wood post witnessed by: Spruce 12 S59W 33 lks.; Spruce 8 N17E 45 lks.
- (L3) Quarter corner common to Sections 1 and 12. 1850: John Burt, DS. Set wood post witnessed by: Tamarack 12 N40W 16 lks.; Tamarack 8 S17E 22 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (K2) No evidence of original survey or subsequent restoration found. Line call south to stream fits fairly well (GLO 1.24 ch.-81.8 feet, measured 92 feet). Line calls in this township were taken on the random lines so true distance from corner to call is not known. Corner position reestablished by single proportion between the northwest and southwest corners of Section 1, and is accepted as a careful and faithful REESTABLISHMENT of the position of the original corner.
- (L3) No evidence of original survey or subsequent restoration found. Corner position reestablished mid-point and on-line between the southeast and southwest corners of Section 1, and is accepted as a careful and faithful REESTABLISHMENT of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|-----------------------------------|------------------------------------|
| (K2) DNR monument | (L3) DNR monument |
| 08" Cherry N82E 21.75' (1/4S,NBT) | 7" B.Spruce N34E 35.0' (1/4S,NBT) |
| 07" Balsam S15W 27.3' (1/4S,NBT) | 7" B.Spruce S73E 39.15' (1/4S,NBT) |
| 10" Spruce S55W 23.6' (1/4S,NBT) | 5" B.Spruce S31W 17.05' (1/4S,NBT) |
| 29" W.Pine N59W 35.3' (1/4S,NBT) | 9" B.Spruce N59W 27.35' (1/4S,NBT) |
- All trees are blazed, scribed and painted. Measurements are to nail in side of tree, bearings are magnetic.



Signed by Paul R. Bressette
 Surveyor's Michigan License No. 37270

Date _____

For the Michigan Department of Natural Resources - Forest Management Division