

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Dickinson

(County)

Located In:

Corner Code #

1. Public Land Survey

T 44N R 27W M1

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling  
in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous  
Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Oct 17 2001

I, Paul R. Bressette, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

(M1) Section corner common to Sections 1, 6, 31 and 36. 1844: Wm. A. Burt, DS. Set wood post witnessed by: Hemlock 20 N17W 44 lks.; Maple 9 S29E 39 lks. 1980: Charles F. Clark, DS. Set 1/2" rebar with cap witnessed by: 6" Spruce North 1.69'; 3" Balsam S65E 10.86'; 6" Balsam S15E 12.36'; 3" Balsam S65W 12.61'. Recorded in L4 RC, p.5.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(M1) Found Clark's rebar as recorded. Found Spruce witness north, down with PK nail in side. No evidence of balsam witnesses found. Measured north to large pine stump 967.4 feet (Clark, GLO 968.2 feet). Retracement south along township line supports this position (wood post 2 feet off line 1 mile south, probable OBT in position for quarter corner one half mile south) and west along township line supports this position (proportioned distance fits well to lake). Based on the evidence found and the measurements, the rebar was replaced with a DNR monument, rewitnessed, and is accepted as a careful and faithful REESTABLISHMENT of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(M1) DNR MONUMENT  
3" Aspen N09E 43.95' (X,NBT)  
3" Balsam S89E 47.9' (X,NBT)  
4" Balsam N74W 62.35' (S36,NBT)  
Wood post N 0.7'

All trees are blazed, scribed and painted. Measurements are to nail in side of tree, bearings are magnetic.



Signed by Paul R. Bressette

Date \_\_\_\_\_

Surveyor's Michigan License No. 37270

For the Michigan Department of Natural Resources - Forest Management Division