

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Dickinson

(County)

Located In:

Corner Code #

1. Public Land Survey

T 44N R 27W M2

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Oct 11 2001

I, Paul R. Bressette, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

(M2) Quarter corner common to Sections 1 and 6. 1844: Wm. A. Burt, DS. Set wood post witnessed by: W.Pine 22 S13W 20 lks.; Y.Birch 10 N17E 17 lks. 1980: Charles F. Clark, RLS. Found and tied in wood post during survey in S36 T45N,R27W.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(M2) No evidence of wood post reported by Clark found. Decayed remains of very large white pine found lying in east-west direction found. No marks are visible and unable to determine exact location of stump. Best estimate of standing location places it in proper position for OBT from calculated position. Distance north to Northeast corner of Section 1 measured 2720.0 feet (Clark 2720.9 feet to found post, GLO 41.30 ch.-2725.8 feet). Corner position established by single proportion between the Southeast corner of Section 12 and the Northeast corner of Section 1, and is accepted as a careful and faithful REESTABLISHMENT of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(M2) DNR monument
 10" Maple N51E 31.6' (1/4S,NBT)
 09" Spruce S66E 18.85' (1/4S,NBT)
 09" Maple S31W 30.1' (1/4S,NBT)
 09" Spruce N53W 8.7' (1/4S,NBT)

All trees are blazed, scribed and painted. Measurements are to nail in side of tree, bearings are magnetic.



Signed by Paul R. Bressette
 Surveyor's Michigan License No. 37270

Date _____

For the Michigan Department of Natural Resources - Forest Management Division