

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Dickinson

(County)

Located In:

Corner Code #

1. Public Land Survey

T 44N	R 27W	M4
T 44N	R 27W	M3
T	R	
T	R	
S	T	R
S	T	R
S	T	R
S	T	R

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Oct 10 2001

I, Paul R. Bressette, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2				
3													
4	7		8		9		10		11				
5													
6	18		17		16		15		14				
7													
8	19		20		21		22		23				
9													
10	30		29		28		27		26				
11													
12	31		32		33		34		35				
13													

A. Description of original monument and accessories and/or subsequent restoration:

- (M4) Quarter corner common to Sections 12 and 7. 1844: Wm. A. Burt, DS. Set wood post witnessed by: W.Pine 6 S57E 4 lks.; W.Pine 8 N72W 16 lks.
- (M3) Section corner common to Sections 1,12,6 and 7. 1844: Wm. A. Burt, DS. Set wood post witnessed by: Y.Pine 14 S62W 14 lks.; Spruce 8 N27E 17 lks. 1850: John Burt, DS. Marked additional witness during subdivision of T44N,R27W: Aspen 12 N29W 13 lks. 1853: Martin M. Hall, DS. Marked additional witness during subdivision of T44N,R26W: W.Pine 14 S59E 22 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (M4) No evidence of original survey or subsequent restoration found. Corner position reestablished by single proportion between the southeast corner of Section 12 and the Northeast corner of Section 1, and is accepted as a careful and faithful REESTABLISHMENT of the position of the original corner.
- (M3) No evidence of original survey found. Found wood post and curved iron 2 feet east of monumented position. Iron was not used since it was found to be a piece of the frame of an old couch found abandoned near the corner. Corner position reestablished by single proportion between the Southeast corner of Section 12 and the Northeast corner of Section 1, and is accepted as a careful and faithful REESTABLISHMENT of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|----------------------------------|---------------------------------|
| (M4) DNR monument | (M3) DNR monument |
| 14" W.Pine N76E 48.2' (1/4S,NBT) | 07" R.Pine N63E 20.15' (S6,NBT) |
| 12" W.Pine S45E 5.55' (1/4S,NBT) | 07" R.Pine S50E 23.35' (S7,NBT) |
| 20" W.Pine S59W 49.7' (1/4S,NBT) | 11" R.Pine S48W 21.8' (S12,NBT) |
| 15" W.Pine N32W 47.4' (1/4S,NBT) | 14" R.Pine N45W 21.3' (S1,NBT) |
- All trees are blazed, scribed and painted. Measurements are to nail in side of tree, bearings are magnetic.



Signed by Paul R. Bressette
 Surveyor's Michigan License No. 37270

Date _____

For the Michigan Department of Natural Resources - Forest Management Division