

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Dickinson

(County)

Located In:

Corner Code #

1. Public Land Survey

T ___ R ___
 T ___ R ___
 T ___ R ___
 T ___ R ___

2. Property Controlling in Section

S 1 T 44N R 27W 8
 S 1 T 44N R 27W 15

3. Miscellaneous Property in Sec.

S ___ T ___ R ___
 S ___ T ___ R ___

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

15 Oct 23 2001

8 Oct 29 2001

I, Paul R. Bressette, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

(8) West One-sixteenth corner of Section 1. Not set in original survey, no evidence of subsequent establishment.

(15) West One-sixteenth corner common to Sections 1 and 12. Not set in original survey, no evidence of subsequent establishment.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(8) Corner position established mid-point and on-line between the West and Center Quarter corners of Section 1.

(15) Corner position established mid-point and on-line between the South Quarter corner and Southwest Section corner of Section 2. Corner falls 40 feet east of left bank of stream.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(8) DNR monument
 12" Maple N56E 23.35' (1/16S,BT)
 07" Spruce S23E 16.05' (1/16S,BT)
 06" Spruce S27W 17.3' (1/16S,BT)
 08" Balsam N46W 20.45' (1/16S,BT)

(15) DNR monument
 17" Tamarack N59E 83.4' (1/16S,BT)
 19" Tamarack S41E 70.4' (1/16S,BT)
 06" Cherry S01W 9.1' (1/16S,BT)
 07" Cherry S81W 15.35' (1/16S,BT)

All trees are blazed, scribed and painted. Measurements are to nail in side of tree, bearings are magnetic.

All trees are blazed, scribed and painted. Measurements are to nail in side of tree, bearings are magnetic.



Signed by Paul R. Bressette
 Surveyor's Michigan License No. 37270

Date _____

For the Michigan Department of Natural Resources - Forest Management Division