

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Dickinson	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 24 T 44N R 28W	12
	S 24 T 44N R 28W	13
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Jeremy J. Pipp, in a field survey on 5/03/2012AD do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(12) Center-South One-Sixteenth corner of Section 24. Not set in original survey. 1993 Michigan DNR (Stephan Szyszkoski PS#33986) Set 1" x 32" iron Pipe capped with 4" dia. Cast Aluminum MDNR tablet witnessed by, 3" Spruce S40E 6.6', 14" Spruce N62E 52.4', 8" W. Birch N05W 27.3', 8" W. Birch S87W 26.6'.

(13) Southeast One-Sixteenth corner of Section 24. Not set in original survey, no evidence of subsequent establishment.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(12) Accepted found MDNR Monument and Four existing Witnesses (two living, two down & dead). Left MDNR monument in place and witnessed.

(13) Corner position established at the intersection of the South and East One-Sixteenth lines of Section 24.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(12) DNR monument
 EX. 16" Spruce N63E 52.87' (1/16S,BT)
 EX. 8" Spruce S37E 6.50' (1/16S,BT)
 6" Spruce N84W 8.55' (1/16S,NBT)
 7" Spruce N30E 17.88' (1/16S,NBT)

All trees are blazed, scribed, and painted. Measurements are to nail in side of tree, bearings are magnetic.

(13) DNR monument
 8" Spruce N58E 26.60' (1/16S,BT)
 11" Spruce S32E 15.17' (1/16S,BT)
 12" Spruce S38W 38.36' (1/16S,BT)
 9" Spruce N76W 46.61' (1/16S,BT)

All trees are blazed, scribed, and painted. Measurements are to nail in side of tree, bearings are magnetic.

Signed by Jeremy J. Pipp
 Surveyor's Michigan License No. 50447



Date July 17, 2012

For the Michigan Department of Natural Resources and Office of Professional Surveyors

20065

20064