

✓

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 46 NR. 24 W.

----- Dickinson ----- COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 10, 11, 14, 15 -----

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass cap -----

WITNESSES TO CORNER 10" Spruce - S 69 W - 34 Links -----

10" Balsam - N 24 E - 23 Links -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established, by double proportionate measurement, by Forestry Division survey crew, while making a partial resurvey of this Township. Burned over land; no original evidence.

Corner was placed and witnessed November 6, 1952.

SURVEYORS SEAL

SIGNED Sean C. DeW DATE 11/26/52
REGISTERED LAND SURVEYOR