

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 44 & 45 N.R. 27 & 28 W


Dickinson & Marquette COUNTY

DESCRIPTION OF CORNER Section Corner for Sections T 45N R28W 36 / 31 T 45N R 27 W

CORNER MONUMENT 1" Iron pipe with 1/4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 10-30-63

WITNESSES TO CORNER..... 7" Basswood (S36)(NBT) N 48° W 14 1/2 links



5" H. Maple (S1) (NBT) S 65° W 13 links

6" H. Maple (S6) (NBT) S 08° E 27 1/2 links

AND  
5" H. Maple (S31) (NBT) N 42° E 15 1/2 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was placed on line and proportioned distance between 1/4 corner  
1/2 mile to west and section corner 1 mile to East.

No original evidence.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE April 13, 1964  
REGISTERED LAND SURVEYOR  
Billy D. Buckler