

✓

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 44 .. NR. 28-29W ..

_ D i c k i n s o n _ _ _ _ _ COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Sections 19 and 24

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap.

WITNESSES TO CORNER 6" Bass Wood (1/4s NBT) .. N 59° E .. 20 1/2 Links

5" H. Maple (1/4s NBT) .. S 71° W .. 70 Links ..

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR
RESTORED. This corner was re-established midway and on line between two Section
Corners. No evidence of original Corner.

Corner was placed and witnessed September 22, 1959.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 4/29/60
REGISTERED LAND SURVEYOR
Billy D. Buckler