

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T~~44~~45 NR 28 W

D i c k i n s o n

M a r q u e t t e

COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 4, 5, 32, 33

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap.

WITNESSES TO CORNER 9" B. Spruce (S 33 NBT) N 43° E 10 Links

8" B. Spruce (S 5 NBT) S 2° W 15 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED. This corner was re-established by single proportionate measure East and West along Township Line. Found old blazes to South also found Iron Pipe 50 Links East and 10 Links South of Corner. No evidence of original corner.

Corner was placed and witnessed September 4, 1959.

SURVEYORS SEAL

SIGNED

Billy D. Buckler
REGISTERED LAND SURVEYOR

Billy D. Buckler

DATE 4/29/60