

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Dickinson

(County)

Located In:

Corner Code #

1. Public Land Survey	T	_____	R	_____	_____		
	T	_____	R	_____	_____		
	T	_____	R	_____	_____		
	T	_____	R	_____	_____		
2. Property Controlling in Section	S	24	T	44	R	28	3
	S	_____	T	_____	R	_____	_____
3. Miscellaneous Property in Sec.	S	_____	T	_____	R	_____	_____
	S	_____	T	_____	R	_____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Stephan J. Szyszkoski, in a field survey on January 21, 1993, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	5	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	15	17	18	19	20	21	22	23	24			
7												
8	19	20	21	22	23	24						
9												
10	30	26	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

(3) North 1/16 corner between Sections 23 and 24. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(3) Found no evidence of prior monumentation or evidence of use at corner location. Established corner midway and on a straight line between Section and Quarter corners 1320.02' north and south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:



(3) Set a 1"x32" iron pipe capped with a 4" dia. cast aluminum MDMR tablet. Blazed and scribed the following:
2" Balsam S64N 5.9' (1/16S BT)
3" Balsam N58W 7.3' (1/16S BT)
3" Spruce N30E 8.2' (1/16S BT)
4" Spruce S59E 2.9' (1/16S BT)
N-S cut line is 22' west.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 2-18-93