

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Dickinson
(County)

1. Public Land Survey	T	44N	R	28N	K7
	T	44N	R	28N	K8
	T	44N	R	28N	K9
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Stephan J. Szyszkoski, in a field survey on January 21, 1993, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	14	15	16	17	18							
7													
8	19	20	21	22	23	24							
9													
10	25	26	27	28	29	30							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(K7) Section corner common to Sections 13-14-23-24. Cedar post placed for the corner in the original survey, 1850. Original BTs: Spruce 15 S49W 31, Spruce 15 N71E 24. Found no subsequent record.
 (K8) Quarter corner common to Sections 23 and 24. Y. Birch post placed for corner in original survey, 1850. BTs: N. Pine 14 S25W 10, Y. Birch 8 N62E 14. Found no subsequent record.
 (K9) Section corner common to Sections 23-24-25-26. Corner established in the original survey in 1850 and perpetuated by Michigan Dept. of Conservation surveyor Dean C. DeLaMater who found remains of one original BT in 1952 and placed a 1" pipe with a 4" brass cap for the corner. No witnesses were taken.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K7) Original post and accessories not recovered. Corner area lies within an old clearcut or burned area. No evidence of original line trees N. pine south or Cedar north. Determined corner to be lost and reestablished same by double proportionate measure to the original record between original corners 1 mile south, 1 mile north, 2 miles west, and a reestablished corner 1 mile east. Stream call B.81 ch. to north checks good with the original record.
 (K8) Original post and accessories not recovered. Found no acceptable evidence of the original corner location on the ground. Reestablished the corner by single proportionate measurement to the original record between section corners 2640.04' north and south. From the corner position thus determined, I found a 1.25" I.D. iron pipe, not of record, 1.7' South and 35.3' East. Similar pipes were found at the S1/16 corner between 23 and 24, and the West 1/16 corner, section 24.
 (K9) Found and accepted a 1" pipe with a 4" brass Mich. Dept. of Conservation cap.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K7) Set 1"x32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet. Blazed and scribed the following:
 6" Spruce N13E 31.6' (S13 NBT)
 4" Spruce N24W 28.3' (S14 NBT)
 4" Spruce S40W 10.8' (S23 NBT)
 2" Balsam S22E 5.7' (S24 NBT)
 N-S cut line 30' West, E-W cut line 31' South.

(K8) Set a 1"x32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet. Blazed and scribed the following:
 4" Spruce N01E 11.8' (1/4S NBT)
 6" Spruce N57W 43.7' (1/4S NBT)
 5" Spruce S70W 34.8' (1/4S NBT)
 4" Balsam S21E 24.7' (1/4S NBT)
 N-S cut line is 15' West.

(K9) Found 1" pipe with 4" brass cap. Blazed and scribed the following:
 4" N. Pine N04W 35.5' (S23 NBT)
 4" Spruce N10E 40.7' (S24 NBT)
 5" Spruce N22W 44.1' (S23 NBT)
 Cut line runs north and east from corner.

Signed by Stephan J. Szyszkoski

Date 2-18-93

Surveyor's Michigan License No. 33986

