

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Dickinson
 (County)

	Located In:	Corner Code #
1. Public Land Survey	T <u>44N</u> R <u>28W</u>	<u>16</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>24</u> T <u>44N</u> R <u>28W</u>	<u>16</u>
	S <u>24</u> T _____ R _____	<u>2</u>
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Stephan J. Szyszkoski, in a field survey on January 21, 1993, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	19	20	21	22	23	24	25	26	27	28
7													
8	18	20	21	22	23	24	25	26	27	28	29	30	31
9													
10	30	29	28	27	26	25	24	23	22	21	20	19	18
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(16) Quarter corner common to Sections 14 and 13. Sugar post placed for corner in original survey, 1850. Bfs: Cedar 12 S48E 38, Spruce 10 S53W 25. Found no subsequent record.
 (16) East 1/16 corner between Sections 24 and 25. Corner not established in the original survey. Found no subsequent record.
 (2) East 1/16 corner between Sections 13 and 24. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(16) Original post and accessories not recovered. Corner location falls in a clearing in a small ravine. Found no evidence of prior monumentation or evidence of use. Determined the corner to be lost and reestablished same by single proportionate measure to the original record between Section corners 2640.04 north and south. From the position established, original stream call south and ridge top north both check.
 (16) Found no evidence of prior monumentation at corner location. Established the corner midway and on a straight line between the Quarter corner 1324.57' west and the Section corner 1324.57' east. The Section corner location was determined by its witness corner recorded in 1985 as follows: 300.00' South of the witness corner on a line projected over the 1/4 Corner on the East side of Sec. 24, and the witness corner.
 (2) Established corner midway and on a straight line between Quarter corner 1321.87' west and Section corner 1321.87' east. From this position, I found a 3/4" iron pipe, not of record, projecting about 4 feet, 5.4' east and 9.6' south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(16) Set 1"x32" iron pipe capped with a 4" dia. cast aluminum NDMR tablet. 6" Spruce N15W 169.7' (1/4S NBT) Chis. "x" on 2"x2.8"x18" high triangular shaped boulder N10W 46.87' Chis. "x" on a projection facing the corner on a 2.8'x4'x3' high boulder, N48W 24.05'.	(16) Set 1"x32" iron pipe capped with a 4" dia. cast aluminum NDMR tablet. Blazed and scribed the following: 14" Cedar N60W 44.0' (1/16S BT) 12" Cedar N01E 41.5' (1/16S BT) 12" Cedar S69E 43.5' (1/16S BT) 14" Cedar S27E 23.4' (1/16S BT) Corner lies approx. 170' SE'ly of the center of NE-SW road.	(2) Set 1"x32" iron pipe capped with a 4" dia. cast aluminum NDMR tablet. 6" Sugar N18W 18.1' (1/16S BT) 5" Balsam N45E 13.7' (1/16S BT) 12" Aspen S07W 19.9' (1/16S BT) 4" Balsam S27E 20.4' (1/16S BT) E-W cut line 7.0' south.
---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 2-18-93

