

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Dickinson <small>(County)</small>	Located in:	Corner Code #
1. Public Land Survey	T 44N R 28W	E9
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on September 28, 1994, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E9) Corner common to Sections 20-21-28-29. Corner re-monumented at the original position as determined from the remains of two original bearing trees in 1952 by Dean C. DeLaMater, ALS. He placed a 1" iron pipe with a 4" Brass cap at the corner and marked as a witness a 9" Balsam NOSE 29 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E9) Found the 1952 monument - a 1" dia. iron pipe capped with a 4" dia. brass Michigan Dept. of Conservation tablet, in good condition, and at record bearing and distance from the 1952 Balsam witness, now dead, and at record bearing and distance from the remains of the two original Cedar bearing trees. The Cedar NE being a stump in good condition, that SW being ground level remains. Left the monument in place and marked four new witnesses as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E9) found 1" iron pipe with 4" brass cap. Blazed and scribed the following new bearing trees:
 5" Maple S52E 6.5'
 6" Spruce S10E 15.7'
 5" Maple S57N 11.9'
 5" Maple N09E 18.0'
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 3-7-95
 Surveyor's Michigan License No. 33986