

56

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Dickinson  
(County)

Located In: Corner Code #

1. Public Land Survey      T 44N R 28W      K1  
   T      R  
   T      R  
   T      R

2. Property Controlling  
   in Section      S      T      R  
                                 S      T      R

3. Miscellaneous  
   Property in Sec.      S      T      R  
                                 S      T      R

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Jun 19 1997

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(K1) Corner common to Sections 1-2 T44N-R28W and Sections 35-36 T45N-R28W. Corner reestablished in 1959 by Billy D. Buckler, RLS: "This corner was re-established by proportionate measure east and west along township line. No evidence of original corner". Buckler placed a 1" Pipe with 4" Brass Cap and marked: 14" White Pine N48W 250 links, 3' high boulder N63W 105 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K1) Found the 1959 monument as described, the cap being a Michigan Dept. of Conservation Forestry Division brass tablet, in good condition, and at record bearing and distance from the 1959 witnesses, both recovered. Although not noted on the 1959 record, a chisled "x" was found on the boulder at record distance. Left the monument in place and marked 3 new accessories as described below. This corner is located on the north edge of a clearing adjacent to an aspen strip to the east. An old junked car (Plymouth) bears S21W 225' (paced). Corner recovered and re-witnessed by B. Wheeler and D. Lampela, Baraga District Office, MDNR. No measurements to other corners were made at this time. This corner is being rerecorded in order to update the accessories.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K1) Found 1" pipe with 4" brass cap.

The 1959 witnesses:

14" W. Pine N42W 250 links

3' High Boulder N56W 105 links

Blazed and scribed the following:

4" Aspen S81E 12.6' "S1 NBT"

3" W. Pine N27W 58.2' "S35 NBT"

3" W. Pine N17E 54.1' "S36 NBT"

Placed a 3" squared post adjacent.

Bearings are magnetic.



Signed by

*Stephan J. Szyszkoski*

Date

9/2/97

Surveyor's Michigan License No.

33986

For the Michigan Department of Natural Resources - Forest Management Division