

57

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Dickinson

(County)

Located In:

Corner Code #

1. Public Land Survey

T44N R 28W L1

T44N R 28W J1

T R

T R

2. Property Controlling  
in Section

S T R

S T R

3. Miscellaneous  
Property in Sec.

S T R

S T R

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Jun 19 1997

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	K	L	M
1											
2	5	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

**A. Description of original monument and accessories and/or subsequent restoration:**

(L1) Quarter corner common to Section 1 T44N-R28W and Section 36 T45N-R28W. Corner monumented by Billy D. Buckler, RLS in 1959: "This corner was replaced from one cedar B.T. bearing N20W 08 links. B.T. in fair condition. Stump out 2 1/2' high. Corner found by forestry Division Survey Crew while running County line". Set 1" Pipe with 4" Brass Cap. 6" Aspen N39E 35.5 links, 14" Aspen N70W 25 links.

(J1) Quarter corner common to Section 2 T44N-R28W and Section 35 T45N-R28W. Corner reestablished in 1959 by Billy D. Buckler, RLS: "This corner was re-established by proportionate measures by two Section corners. No evidence of original corner". Buckler set a 1" pipe with 4" brass cap and marked the following: 18" R.Pine N23W 285 links, 22" R.Pine S65W 300 links.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(L1) Recovered the 1959 monument, as described, the cap being a cast Michigan Dept. of Conservation Forestry Division tablet, at record bearing and distance from the remains of the 1959 witnesses, now both dead and down. Scribing still visible on the aspen remains. Left the monument in place and marked 4 new witnesses as described below. Corner recovered and re-witnessed by B.Wheeler and D.Lampela, Baraga District Office, MDNR. No measurements to other corners were made at this time. This corner is being rerecorded in order to update the accessories.

(J1) Found the 1959 monument as described, the cap being a cast brass Michigan Dept. of Conservation Forestry Division tablet, in good condition, at record bearing and distance from the 1959 witnesses, both in good condition. Left the monument in place and marked two new accessories as described below. Corner is located in a small clearing approx. 200' (paced) south of E-W trail road. Corner recovered and re-witnessed by D.Lampela and B.Wheeler, Baraga District Office, MDNR. No measurements to other corners were made at this time. This corner is being rerecorded in order to update the accessories.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(L1) Found 1" pipe with 4" brass cap.

Blazed and scribed the following:

9" Red Maple N62W 15.6' 1/4S NBT"

5" B.Ash S77W 18.2' 1/4S NBT"

5" B.Ash S60E 19.1' 1/4S NBT"

7" Twin B.Ash N62E 21.5' 1/4S NBT"

Bearings are magnetic.

(J1) Found 1" pipe with 4" brass cap.

The 1959 witnesses:

24" R.Pine N18W 285 links

28" R.Pine S70W 300 links


Blazed and scribed the following:

5" White Pine S87W 71.5' 1/4S NBT"

4" R.Pine N48E 59.1' 1/4S NBT"

Placed a 3" squared post adjacent.

Bearings are magnetic.



Signed by

Stephan J. Szyszkoski

Date

9/2/97

Surveyor's Michigan License No.

33986

For the Michigan Department of Natural Resources - Forest Management Division